



MET Laboratories, Inc. *Safety Certification - EMI - Telecom Environmental Simulation*

914 WEST PATAPSCO AVENUE • BALTIMORE, MARYLAND 21230-3432 • PHONE (410) 354-3300 • FAX (410) 354-3313

33439 WESTERN AVENUE • UNION CITY, CALIFORNIA 94587 • PHONE (510) 489-6300 • FAX (510) 489-6372

3162 BELICK STREET • SANTA CLARA, CALIFORNIA 95054 • PHONE (408) 748-3585 • FAX (510) 489-6372

August 22, 2011

Ubiquiti Networks
91 E. Tasman
San Jose, CA 95134

Dear Jennifer Sanchez,

Enclosed is the EMC test report for compliance testing of the Ubiquiti Networks, WispStation5, tested to the requirements of ETSI EN 301 489-1 with ETSI EN 301 489-17 (Article 3.1(b) of R&TTE Directive).

Thank you for using the services of MET Laboratories, Inc. If you have any questions regarding these results or if MET can be of further service to you, please feel free to contact me.

Sincerely yours,
MET LABORATORIES, INC.

Jennifer Warnell
Documentation Department

Reference: (\ Ubiquiti Networks \ EMCS83056-ETS489)

Certificates and reports shall not be reproduced except in full, without the written permission of MET Laboratories, Inc. This letter of transmittal is not part of the attached report.

The Nation's First Licensed Nationally Recognized Testing Laboratory



MET Laboratories, Inc. *Safety Certification - EMI - Telecom Environmental Simulation*

914 WEST PATAPSCO AVENUE • BALTIMORE, MARYLAND 21230-3432 • PHONE (410) 354-3300 • FAX (410) 354-3313

33439 WESTERN AVENUE • UNION CITY, CALIFORNIA 94587 • PHONE (510) 489-6300 • FAX (510) 489-6372

3162 BELICK STREET • SANTA CLARA, CALIFORNIA 95054 • PHONE (408) 748-3585 • FAX (510) 489-6372

Electromagnetic Compatibility Test Report

For the

**Ubiquiti Networks
WispStation5**

Tested for Compliance with

ETSI EN 301 489-1

With ETSI EN 301 489-17 (Article 3.1(b) of R&TTE Directive)

MET Report: EMCS83056-ETS489

August 22, 2011

Prepared For:

**Ubiquiti Networks
91 E. Tasman
San Jose, CA 95134**

Prepared By:
MET Laboratories, Inc.
914 W. Patapsco Ave
Baltimore, MD 21230

Electromagnetic Compatibility Test Report

For the

**Ubiquiti Networks
WispStation5**

Tested for Compliance with

ETSI EN 301 489-1

With ETSI EN 301 489-17 (Article 3.1(b) of R&TTE Directive)

MET Report: EMCS83056-ETS489



Jonathan Chao, Project Engineer
Electromagnetic Compatibility Lab



Jennifer Warnell
Documentation Department

Engineering Statement: The measurements shown in this report were made in accordance with the procedures indicated, and the emissions from this equipment were found to be within the limits applicable. I assume full responsibility for the accuracy and completeness of these measurements, and for the qualifications of all persons taking them. It is further stated that upon the basis of the measurements made, the equipment tested is capable of operation in accordance with the requirements of ETSI EN 301 489-1 with ETSI EN 301 489-17 under normal use and maintenance.



Shawn McMillen,
Wireless Manager, Electromagnetic Compatibility Lab

Report Status Sheet

Revision	Report Date	Reason for Revision
Ø	August 22, 2011	Initial Issue.

Table of Contents

1.0	Introduction.....	1
1.1	Overview	1
1.2	Test Site	1
1.3	General Performance Criteria	1
1.4	Testing Summary.....	2
1.5	Modifications to the Test Standard.....	3
1.6	References	3
2.0	Equipment Under Test	4
2.1	Description of Test Sample	4
2.2	Equipment Configuration	5
2.3	Support Equipment.....	5
2.4	Ports and Cabling Information.....	5
2.5	Mode of Operation.....	5
2.6	Modifications to the EUT	5
2.7	Disposition of EUT.....	5
3.0	Electromagnetic Compatibility Emission Criteria.....	6
3.1	AC Mains Power Input/Output Ports: Limits for Conducted Emissions	6
3.2	Harmonic Current Emissions.....	10
3.3	Voltage Fluctuations (Flicker).....	13
3.4	Telecommunications Ports.....	16
4.0	Electromagnetic Compatibility Immunity Criteria	19
4.1	Radio Frequency Electromagnetic Field.....	19
4.2	Electrostatic Discharge	21
4.3	Fast Transient, Common Mode	27
4.4	Radio Frequency, Common Mode.....	31
4.5	Voltage Dips and Short Interruptions	34
4.6	Surges	36
5.0	Test Equipment.....	41

List of Tables

Table 1. Summary of Compliance Testing	2
Table 2. Test References	3
Table 3. Equipment Configuration	5
Table 4. Support Equipment	5
Table 5. Ports and Cabling Information	5
Table 6. Limits of Conducted Disturbance at AC Mains Power Input/Output Ports	6
Table 7. Conducted Emissions - Voltage, Worst Case Emissions, AC Power, Phase Line	7
Table 8. Conducted Emissions - Voltage, Worst Case Emissions, AC Power, Neutral Line	8
Table 9. Harmonic Current Emission Limits from Section 7 of EN 61000-3-2	10
Table 10. Harmonics, Test Results	11
Table 11. Flicker, Test Results	14
Table 12. Limits of Conducted Common Mode (Asymmetric Mode) Disturbance at Telecommunication Ports from Clause 5.2 of EN 55022 Class B	16
Table 13. Limits for Conducted Disturbance at Telecommunication Ports Test Results, 230 VAC 50 Hz Telecom	17
Table 14. Radiated Immunity, Test Results	19
Table 15. Electrostatic Discharge, Test Results	22
Table 16. Fast Transient, Test Results	29
Table 17. Conducted Immunity, Test Results	32
Table 18. Voltage Dips and Short Interruptions Limits	34
Table 19. Voltage Dips and Interruptions, Test Results	34
Table 20. Combination Wave Generator Test Parameters for EN 61000-4-5	36
Table 21. Surges, Test Results	39

List of Figures

Figure 1. Block Diagram of Test Configuration	4
Figure 2. Test Circuit for EN 61000-3-3	13
Figure 3. EN 61000-4-4 Test Waveform	28
Figure 4. EN 61000-4-5 Surge Test Waveforms	37

List of Photographs

Photograph 1. AC Mains Power Input/Output Ports, Conducted Disturbance, Test Setup 1	9
Photograph 2. AC Mains Power Input/Output Ports, Conducted Disturbance, Test Setup 2	9
Photograph 3. Harmonic Current Emissions, Test Setup	12
Photograph 4. Voltage Fluctuations (Flicker), Test Setup	15
Photograph 5. Limits for Conducted Disturbance at Telecommunication Ports 1	18
Photograph 6. Limits for Conducted Disturbance at Telecommunication Ports 2	18
Photograph 7. Radio Frequency Electromagnetic Field, Test Setup	20
Photograph 8. Radio Frequency Electromagnetic Field, Test Setup, High Frequency	20
Photograph 9. ESD, Test Points, Back POE	23
Photograph 10. ESD, Test Points, Front POE	23
Photograph 11. ESD, Test Points, Front View	24
Photograph 12. ESD, Test Points, Left POE	24
Photograph 13. ESD, Test Points, Right POE	25
Photograph 14. ESD, Test Points, Top POE	25
Photograph 15. Electrostatic Discharge, Test Setup	26
Photograph 16. Fast Transient, Common Mode, Test Setup	30
Photograph 17. Fast Transient, Common Mode, Telecom Setup	30
Photograph 18. Radio Frequency, Common Mode, Test Setup	33
Photograph 19. Radio Frequency, Common Mode, Telecom Setup	33
Photograph 20. Voltage Dips and Interruptions, Test Setup	35
Photograph 21. Surges, Test Setup	40
Photograph 22. Surges, I/O Test Setup	40

List of Terms and Abbreviations

AC	Alternating Current
ACF	Antenna Correction Factor
Cal	Calibration
<i>d</i>	Measurement Distance
dB	Decibels
dBμA	Decibels above one microamp
dBμV	Decibels above one microvolt
dBμA/m	Decibels above one microamp per meter
dBμV/m	Decibels above one microvolt per meter
DC	Direct Current
E	Electric Field
DSL	Digital Subscriber Line
ESD	Electrostatic Discharge
EUT	Equipment Under Test
<i>f</i>	Frequency
CISPR	Comite International Special des Perturbations Radioelectriques (International Special Committee on Radio Interference)
GRP	Ground Reference Plane
H	Magnetic Field
HCP	Horizontal Coupling Plane
Hz	Hertz
IEC	International Electrotechnical Commission
kHz	kiloHertz
kPa	kiloPascal
kV	kilovolt
LISN	Line Impedance Stabilization Network
MHz	MegaHertz
μH	microHenry
μF	microFarad
μs	microseconds
PRF	Pulse Repetition Frequency
RF	Radio Frequency
RMS	Root-Mean-Square
V/m	Volts per meter
VCP	Vertical Coupling Plane

1.0 Introduction

1.1 Overview

MET Laboratories, Inc. was contracted by Ubiquiti Networks to perform testing on the WispStation5, under Ubiquiti Networks purchase order number US100133/US100132.

This document describes the test setups, test methods, required test equipment, and the test limit criteria used to perform compliance testing of the WispStation5.

The results obtained relate only to the item(s) tested.

Model(s) Tested:	WispStation5
Model(s) Covered:	WispStation5
EUT Specifications:	Primary Power: 230 VAC, 50 Hz
	Secondary Power: N/A
	Equipment Emissions Class: The radio equipment and/or associated ancillary equipment under test are classified as equipment for fixed use
Lab Ambient Test Conditions:	Temperature: 15-35° C
	Relative Humidity: 30-60%
	Atmospheric Pressure: 860-1060 mbar
Evaluated by:	Jonathan Chao
Report Date(s):	August 22, 2011

1.2 Test Site

Testing was performed at MET Laboratories, Inc., 3162 Belick St. Santa Clara, CA 95054. All equipment used in making physical determinations is accurate and bears recent traceability to the National Institute of Standards and Technology.

1.3 General Performance Criteria

The performance criteria cited in EN 301 489-17:

- performance criteria A for immunity tests with phenomena of a continuous nature;
- performance criteria B for immunity tests with phenomena of a transient nature;
- performance criteria C for immunity tests with power interruptions exceeding a certain time.

Note: For specific details on performance criteria, see sub-clause 6.2 of EN 301 489-17.

1.4 Testing Summary

Emissions

Descriptive Name	Requirement	Test Method	Result
Enclosure of Ancillary Equipment Measured on a Stand Alone Basis	ETSI EN 301 489-1, Section 8.2	EN 55016-2-3 (2006)	Not Applicable - Only applicable for ancillary equipment.
DC Power Input/Output Ports	ETSI EN 301 489-1, Section 8.3	EN 55022 (2006)	Not Applicable - EUT does not run on DC power.
AC Mains Power Input/Output Ports	ETSI EN 301 489-1, Section 8.4	EN 55022 (2006)	Compliant
Harmonic Current Emissions (AC Mains Input Port)	ETSI EN 301 489-1, Section 8.5	EN 61000-3-2 +A1 (2006)	Compliant
Voltage Fluctuations and Flicker (AC Mains Input Port)	ETSI EN 301 489-1, Section 8.6	EN 61000-3-3 (1995)	Compliant
Telecommunication Ports	ETSI EN 301 489-1, Section 8.7	EN 55022 (2006)	Compliant

Immunity

Descriptive Name	Requirement	Test Method	Result
Radio Frequency Electromagnetic Field (80 MHz – 1000 MHz and 1400 MHz to 2700 MHz)	ETSI EN 301 489-1, Section 9.2	EN 61000-4-3 (2006)	Compliant
Electrostatic Discharge (ESD)	ETSI EN 301 489-1, Section 9.3	EN 61000-4-2 (2001)	Compliant
Fast Transient, Common Mode	ETSI EN 301 489-1, Section 9.4	EN 61000-4-4 (2004)	Compliant
Radio Frequency, Common Mode	ETSI EN 301 489-1, Section 9.5	EN 61000-4-6 (2005)	Compliant
Transient & Surges in the Vehicular Environment	ETSI EN 301 489-1, Section 9.6	ISO 7637-2 (2004) (12/24 VDC)	Not Applicable - EUT not meant to be used in a vehicular environment.
Voltage Dips and Interruptions	ETSI EN 301 489-1, Section 9.7	EN 61000-4-11 (2004)	Compliant
Surges	ETSI EN 301 489-1, Section 9.8	EN 61000-4-5 (2006)	Compliant

Table 1. Summary of Compliance Testing

1.5 Modifications to the Test Standard

No modifications were made to the test standard.

1.6 References

ETSI EN 301 489-1 V1.8.1 (2008-04)	Electromagnetic compatibility and Radio spectrum Matters (ERM); Electromagnetic Compatibility (EMC) standard for radio equipment and services; Part 1: Common technical requirements
ETSI EN301 489-17 V2.1.1(2009-05)	Electromagnetic compatibility and Radio spectrum Matters (ERM); Electromagnetic Compatibility (EMC) standard for radio equipment and services; Part 17: Specific conditions for Wideband data and HIPERLAN equipment
EN 55022	Information Technology Equipment – Radio Disturbance Characteristics – Limits and Methods of Measurement, 2006
EN 61000-3-3	Electromagnetic Compatibility (EMC) Part 3-3: Limits – Limitation of Voltage Changes, Voltage Fluctuations and Flicker in Public Low-Voltage Supply Systems, for Equipment with Rated Current ≤ 16 A per Phase and Not Subject to Conditional Connection, 1995
EN 61000-4-2	Electromagnetic Compatibility (EMC) Part 4-2: Testing and Measurement Techniques – Electrostatic Discharge Immunity Test, 2001
EN 61000-4-3	Electromagnetic compatibility (EMC) Part 4-3: Testing and Measurement Techniques – Radiated, Radio-Frequency, Electromagnetic Field Immunity Test, 2006
EN 55016-2-3	Specification for Radio Disturbance and Immunity Measuring Apparatus and Methods – Part 2-3: Methods of Measurement of Disturbances and Immunity – Radiated Disturbance Measurements, 2006
EN 61000-4-4	Electromagnetic Compatibility (EMC) Part 4-4: Testing and Measurement Techniques – Electrical Fast Transient/Burst Immunity Test, 2004
EN 61000-4-5	Electromagnetic Compatibility (EMC) Part 4-5: Testing and Measurement Techniques – Surge Immunity Test, 2006
EN 61000-4-6	Electromagnetic Compatibility - Part 4-6: Testing and Measurement Techniques Section – Immunity to Conducted Disturbances, Induced by Radio-Frequency Fields, 2005
EN 61000-4-11	Electromagnetic Compatibility - Part 4-11: Testing and Measurement Techniques – Voltage Dips, Short Interruptions and Voltage Variations Immunity Tests, 2004
ISO 7637-2	Road Vehicles – Electrical Disturbances from Conduction and Coupling – Part 2: Electrical Transient Conduction Along Supply Lines Only, 2004
EN 61000-3-2/Amendment 1	Electromagnetic Compatibility (EMC) – Part 3-2: Limits – Limits for Harmonic Current Emissions (Equipment Input Current Up to and Including 16 A per Phase, 2006

Table 2. Test References

2.0 Equipment Under Test

2.1 Description of Test Sample

The Ubiquiti Networks, Inc. WispStation5, Equipment Under Test (EUT), is a 802.11a Long-Range 5GHz Station.




Figure 1. Block Diagram of Test Configuration

2.2 Equipment Configuration

The EUT was set up as outlined in Figure 1. All equipment incorporated as part of the EUT is included in the following list.

Name / Description	Model Number	Serial Number
WispStation5	WS5	MM100027314781

Table 3. Equipment Configuration

2.3 Support Equipment

Support equipment necessary for the operation and testing of the EUT is included in the following list.

Name / Description	Manufacturer	Model Number
Laptop	Dell	Inspiron
POE	Ubiquiti Networks	UBI-POE-24-5

Table 4. Support Equipment

2.4 Ports and Cabling Information

Port Name on EUT	Cable Description	Qty.	Length (m)	Shielded (Y/N)	Termination Point
1	Ethernet	1	3	Y	POE

Table 5. Ports and Cabling Information

2.5 Mode of Operation

The EUT operates in OFDM mode with 20 MHz channel bandwidths. EUT was configured to transmit continuously for testing purposes.

2.6 Modifications to the EUT

No modifications were made to the EUT.

2.7 Disposition of EUT

The test sample including all support equipment submitted to the Electro-Magnetic Compatibility Lab for testing was returned to Ubiquiti Networks upon completion of testing.

3.0 Electromagnetic Compatibility Emission Criteria

3.1 AC Mains Power Input/Output Ports: Limits for Conducted Emissions

Test Requirement(s): ETSI EN 301 489-1, Clause 8.4:

In accordance with *EN 55022 Clause 5.1*, the EUT shall meet the Class B limits shown in Table 6:

Limits for Conducted Emissions of Equipment				
Frequency Range (MHz)	intended for use in telecommunication centres only [EN 55022 Class A Limits] (dB μ V)		[EN 55022 Class B Limits] (dB μ V)	
	Quasi-Peak	Average	Quasi- Peak	Average
0.15 - 0.5	79	66	66 to 56	56 to 46
0.5 - 5	73	60	56	46
5 - 30	73	60	60	50

Table 6. Limits of Conducted Disturbance at AC Mains Power Input/Output Ports

Note: The lower limit shall apply at the transition frequencies. The limits decrease linearly with the logarithm of the frequency in the range of 0.15 MHz to 0.5 MHz.

Test Procedure:

The EUT was placed on a non-metallic table located in a shielded enclosure (See Photograph 1). The measurement was performed using normal operation of the equipment. The method of testing, test conditions, and test procedures of *Clause 9* of *EN 55022* were used. The EMC receiver scanned the frequency range from 150 kHz to 30 MHz. The measurements were performed over the frequency range of 0.15 MHz to 30 MHz using a 50 Ω / 50 μ H as the input transducer to an EMC field intensity meter. The tests were conducted in a RF-shielded enclosure.

Test Results:

The EUT was compliant with the specified requirements of Clause 8.4.

Test Engineer(s):

Jonathan Chao

Test Date(s):


06/21/11

Electromagnetic Compatibility Emission

AC Mains Power Input/Output Ports: Limits for Conducted Emissions

Line	Freq. (MHz)	QP Amplitude (dBuV)	QP Limit (dBuV)	Delta (dB)	Pass	Average Amplitude (dBuV)	Average Limit (dBuV)	Delta (dB)	Pass
WS 5 230 VAC 50 Hz Line	.352	44.69	58.934	-14.244	Pass	35.96	48.934	-12.974	Pass
WS 5 230 VAC 50 Hz Line	.725	36.35	56	-19.65	Pass	28.72	46	-17.28	Pass
WS 5 230 VAC 50 Hz Line	1.155	34.77	56	-21.23	Pass	25.85	46	-20.15	Pass

Table 7. Conducted Emissions - Voltage, Worst Case Emissions, AC Power, Phase Line




Plot 1. Conducted Emission Limits, Phase Line Plot

Electromagnetic Compatibility Emission

AC Mains Power Input/Output Ports: Limits for Conducted Emissions

Line	Freq. (MHz)	QP Amplitude (dBuV)	QP Limit (dBuV)	Delta (dB)	Pass	Average Amplitude (dBuV)	Average Limit (dBuV)	Delta (dB)	Pass
WS 5 230VAC 50Hz Neutral	.371	51.33	58.499	-7.169	Pass	42.98	48.499	-5.519	Pass
WS 5 230 VAC 50 Hz Neutral	.768	42.8	56	-13.2	Pass	35.91	46	-10.09	Pass
WS 5 230 VAC 50 Hz Neutral	1.748	41.25	56	-14.75	Pass	32.77	46	-13.23	Pass

Table 8. Conducted Emissions - Voltage, Worst Case Emissions, AC Power, Neutral Line



Plot 2. Conducted Emission Limits, Neutral Line Plot

AC Mains Power Input/Output Ports: Limits for Conducted Emissions



Photograph 1. AC Mains Power Input/Output Ports, Conducted Disturbance, Test Setup 1



Photograph 2. AC Mains Power Input/Output Ports, Conducted Disturbance, Test Setup 2

Electromagnetic Compatibility Emission

3.2 Harmonic Current Emissions

Test Requirement(s): ETSI EN 301 489-1, Clause 8.5:

Per *EN 61000-3-2+A1, Clause 7*, the EUT must not produce harmonic currents, which exceed the limits expressed in Table 9.

Harmonic Order	Maximum Permissible Harmonic Current (in Amperes)
Odd Harmonics	
3	2.30
5	1.14
7	0.77
9	0.40
11	0.33
13	0.21
$15 < n < 39$	$0.15 - 15/n$
Harmonic Order	Maximum Permissible Harmonic Current (in Amperes)
Even Harmonics	
2	1.08
4	0.43
6	0.30
$8 < n < 40$	$0.23 - 8/n$

Table 9. Harmonic Current Emission Limits from Section 7 of EN 61000-3-2

Test Procedure:

The EUT was placed on a non-metallic table located in a shielded enclosure (See Photograph 3). The measurement was performed using normal operation of the equipment. The method of testing, test conditions, and test procedures of *EN 61000-3-2+A1*.

Electromagnetic Compatibility Emission

Harmonic Current Emissions

Test Procedure (Con't): ITE is tested with the equipment configured to its rated current. In this case, the equipment, if necessary, may be configured with its power supplies loaded with additional load (resistive) boards to simulate rated current conditions. For ITE systems designed for use with a manufacturer-supplied power distribution system, e.g. transformers, UPS, power conditioner, etc., compliance with the limits of this standard shall be met at the input to the power distribution system.

Test Results: The EUT was found compliant with the specified requirements of Clause 8.5.

Test Engineer(s): Jonathan Chao

Test Date(s): 06/22/11

Class (A, B, C, D)	Voltage (V)	Current (A)	Frequency (Hz)	Total Harmonic Distortion (%)
A	243.7 V	33.62 mA	49.996 Hz	248.23%
Harmonic #	Measured (A)	Limit(A)✧	Results	Notes
3	.01254	2.300	Pass	No anomalies
5	.01216	1.140	Pass	No anomalies
7	.01163	0.770	Pass	No anomalies
9	.01095	0.400	Pass	No anomalies
11	.01015	0.330	Pass	No anomalies
13	.00924	0.21	Pass	No anomalies
15-39	.00044-.00826	0.150- 0.058	Pass	No anomalies
2	.00168	1.080	Pass	No anomalies
4	.00166	0.430	Pass	No anomalies
6	.00162	0.300	Pass	No anomalies
8-40	.00044-.00153	0.230- 0.046	Pass	No anomalies

Table 10. Harmonics, Test Results



Photograph 3. Harmonic Current Emissions, Test Setup

Electromagnetic Compatibility Emission

3.3 Voltage Fluctuations (Flicker)

Test Requirement(s): ETSI EN 301 489-1, Clause 8.6:

The EUT must not produce voltage fluctuations and/or flicker at the supply terminals as measured or calculated according to clause 4, according to limits expressed in *Clause 5*, under test conditions described in *Clause 6* and *Annex A* of *EN 61000-3-3*.

Test Procedure:

The EUT was placed on a non-metallic table inside a shielded enclosure (See Photograph 4). The EUT was situated such that the sides of the EUT were no closer than 2.0 m from the walls of the shielded enclosure. The EUT was operated with an AC main source at 220 V. Tests to prove the compliance of the EUT with the limits of *EN 61000-3-3*, *Section 5* were made using the test circuit provided in Figure 2 of *EN 61000-3-3*. The test circuit consisted of the test power supply, the reference impedance, the EUT, and a flickermeter. The test supply voltage (open-circuit voltage) was the rated voltage of the equipment. The test voltage was maintained within 2% of the nominal value. The frequency was 50 Hz \pm 0.5%. The total harmonic distortion of the supply voltage was less than 3%. The limits applicable to voltage fluctuations and flicker at the supply terminals of the EUT were automatically measured with the analyzer.




Figure 2. Test Circuit for EN 61000-3-3

Electromagnetic Compatibility Emission

Voltage Fluctuations (Flicker)


Test Results: The EUT was found compliant with the specified requirements of Clause 8.6.

Test Engineer(s): Jonathan Chao

Test Date(s): 06/22/11

Voltage (V)		Current (A)	Frequency (Hz)	Power Factor	
243.7 V		34.47 mA	50.002 Hz	.367	
Average (Is) relative voltage Drop			d(t)	.002%	
Relative voltage fluctuation (3s)			Dpp	.001	
d(t) at steady - state level			YES /NO	Yes	
Last relative steady - state level change			Dc	0%	
Last transition swing			Dmax	--	
Normalized peak flicker (3s)			Pp	0%	
Parameter			Observation Period	Limit	
			Short	Long	
Observation Time	Tp		10 min	120 min	
Maximum relative voltage change	Dmax		0%	0%	4
Max rel. steady-state voltage change	Dc		0%	0%	3
Duration of d(t) > 3 %	T		0s	0s	0.2
Short term flicker severity	Pst		0	0	1.0
Long term flicker severity	Plt		NA	0	0.65

Table 11. Flicker, Test Results



Photograph 4. Voltage Fluctuations (Flicker), Test Setup

Electromagnetic Compatibility Emission

3.4 Telecommunications Ports

Test Requirement(s): ETSI EN 301 489-1, Clause 8.7:

The EUT must be in accordance with EN 55022 (2006), Section 5.2.

The EUT shall meet the Conducted Common Mode limits shown in Table 12:

Frequency Range (MHz)	Voltage Limits (dB μ V)		Current Limits (dB μ A)	
	Quasi-Peak	Average	Quasi- Peak	Average
0.15 - 0.5	84 to 74	74 to 64	40 to 30	30 to 20
0.5 - 30	74	64	30	20
Note: The limits decrease linearly with the logarithm of the frequency in the range of 0.15 MHz to 0.5 MHz. The current and voltage disturbance limits are derived for use with an ISN which presents a common mode (asymmetric mode) impedance of 150 Ω to the telecommunication port under test (conversion factor is $20 \text{ Log}_{10} 150/1 = 44 \text{ dB}$).				

Table 12. Limits of Conducted Common Mode (Asymmetric Mode) Disturbance at Telecommunication Ports from Clause 5.2 of EN 55022 Class B

Test Procedure:

The EUT was placed on a non-metallic table located in a shielded enclosure (See Photograph 5). The measurements were performed using normal operation of the equipment. The method of testing, test conditions, and test procedures of *Clause 9* of *EN 55022* were used. The EMC receiver scanned the frequency range from 150 kHz to 30 MHz. The measurements were performed over the frequency range of 0.15 MHz to 30 MHz using an ISN, Current Probe or Capacitive Voltage Probe as the input transducer to an EMC field intensity meter.

Environmental Conditions for Conducted Emission	
Ambient Temperature:	25°C
Relative Humidity:	35%

Test Results:

The EUT was found compliant with the requirement(s) of this section.

Test Engineer(s):

Jonathan Chao

Test Date(s):


06/21/11

Limits for Conducted Disturbance at Telecommunication Ports

Conducted Emissions - Voltage for Telecommunication Ports, Worst Case Emissions, 230 VAC 50 Hz Telecom Line

Line	Frequency (MHz)	Raw (dBuV)	QP Amplitude (dBuV)	QP Limit (dBuV)	Delta (dB)	Pass / Fail	Raw (dBuV)	Average Amplitude (dBuV)	Average Limit (dBuV)	Delta (dB)	Pass / Fail
230VAC 50Hz Telecom	.166	32.78	0.78	39.158	-38.378	Pass	31.96	-3.99	29.158	-29.198	Pass
230VAC 50Hz Telecom	.219	22.61	-9.39	36.857	-46.247	Pass	19.25	-12.75	26.857	-39.607	Pass
230VAC 50Hz Telecom	.751	16.85	-15.15	30	-45.15	Pass	10.89	-21.11	20	-41.11	Pass
230VAC 50Hz Telecom	2.08	19.84	-12.16	30	-42.16	Pass	14.16	-17.84	20	-37.84	Pass
230VAC 50Hz Telecom	8.2	31.09	-0.91	30	-30.91	Pass	26.87	-5.13	20	-25.13	Pass
230VAC 50Hz Telecom	25.69	30.73	-1.27	30	-31.27	Pass	28.41	-3.59	20	-23.59	Pass

Table 13. Limits for Conducted Disturbance at Telecommunication Ports Test Results, 230 VAC 50 Hz Telecom



Plot 3. Conducted Emission Limits for Telecommunications Ports, 230 VAC 50 Hz Telecom Plot

Limits for Conducted Disturbance at Telecommunication Ports



Photograph 5. Limits for Conducted Disturbance at Telecommunication Ports 1



Photograph 6. Limits for Conducted Disturbance at Telecommunication Ports 2

4.0 Electromagnetic Compatibility Immunity Criteria

4.1 Radio Frequency Electromagnetic Field

Test Requirement(s): ETSI EN 301 489-1, Clause 9.2:

Per ETSI EN 301 489-1, the EUT must not be susceptible to a radiated electromagnetic field of 3 V/m, 80% amplitude modulated, in the frequency range 80 MHz to 1000 MHz and 1400MHz to 2700MHz (EN 61000-4-3). Performance criterion A applies.

The EUT was placed on a non-metallic table in the center of a 20' x 12' x 8' enclosure, and the radiating antenna was placed 3 m in front of the EUT (See Photograph 7). Support equipment for the EUT was located outside of the test room. The EUT was exposed to the required immunity fields. The amplitude and frequency of the radiated interference was set by an automated, computer-controlled system.

The chamber and signal generation/amplification system is calibrated to insure a uniform RF field with no EUT present. The recorded signal is played back by the controlling computer with the EUT placed in the area of uniform field. The signal source was stepped through the applicable frequency range at a rate no faster than 1% of the fundamental, as recommended in EN 61000- 4-3. The signal was amplitude modulated 80% over the frequency range 80 MHz to 1000 MHz at a level of 3 V/m. Field presence was monitored during testing via a field probe placed in close proximity to the EUT. Throughout testing, the EUT was closely monitored for signs of susceptibility. The test was performed with the antennae oriented in both a horizontal and vertical polarization. Testing was performed in a semi-anechoic chamber.

Test Results: The EUT as tested was compliant with the requirements of Clause 9.2.

Test Engineer(s): Jonathan Chao

Test Date(s): 06/21/11

Start Frequency (MHz)	Stop Frequency (MHz)	Severity (V/m)	Polarity (H/V)	Modulation (Freq & Type)	Results			
					Front	Back	Left	Right
80	1000	3	V	1 kHz, 80%AM	Pass	Pass	Pass	Pass
80	1000	3	H	1 kHz, 80%AM	Pass	Pass	Pass	Pass
1400	2700	3	V	1 kHz, 80%AM	Pass	Pass	Pass	Pass
1400	2700	3	H	1 kHz, 80%AM	Pass	Pass	Pass	Pass

Table 14. Radiated Immunity, Test Results

Radio Frequency Electromagnetic Field



Photograph 7. Radio Frequency Electromagnetic Field, Test Setup



Photograph 8. Radio Frequency Electromagnetic Field, Test Setup, High Frequency

Electromagnetic Compatibility Immunity

4.2 Electrostatic Discharge

Test Requirement(s): ETSI EN 300 489-1 Clause 9.3:

Per *EN 61000-4-2*, the EUT was tested with air discharges of up to ± 8 kV, applied to non-conductive surfaces, and to contact discharges of up to ± 4 kV, applied to conductive surfaces of the EUT and the VCP. Performance Criterion B applies.

The EUT was placed on a metallic table located above a ground reference plane (GRP) (See Photograph 15), with a thickness of at least 0.25 mm, thus satisfying the requirements of *IEC 61000-4-2*:

If [the GRP] shall be a metallic sheet (copper or aluminum) of 0.25 mm minimum thickness.... The minimum size of the reference plane is 1 m x 1 m, the exact size depending on the dimensions of the EUT. It shall project beyond the EUT or coupling plane by at least 0.5 m on all sides....

A horizontal coupling plane (HCP), 1.6 m x 0.8 m, shall be placed on the table. The EUT and cables shall be isolated from the coupling plane by an insulating support 0.5 mm thick.

A copper vertical coupling plane (VCP) measuring 0.5 m X 0.5 m was placed 0.1 m from the EUT. The VCP was connected to the GRP through two series 470 k Ω resistors. The GRP was connected to safety ground. The EUT was connected to the grounding system through its power cable only, in accordance with *EN 61000-4-2, Section 7.1, paragraph 4*:

The EUT shall be connected to the grounding system in accordance with its installation specifications. No additional grounding connections are allowed.

Ambient Temperature:	21.6°C
Relative Humidity:	35%
Atmospheric Pressure:	101.9 kPa

Environmental Conditions during EN 61000-4-2 Testing

Electromagnetic Compatibility Immunity

Electrostatic Discharge

Test Procedure: Air discharges of up to $\pm 8\text{kV}$ were applied to non-conductive surfaces. Contact discharges of up to $\pm 4\text{kV}$ were applied to conductive surfaces of the EUT. Contact discharges of $\pm 4\text{kV}$ were applied to the VCP. Negative and positive discharges were applied at least ten times to each selected discharge point. The functionality of the EUT was determined during and after each discharge.

Test Results: The EUT as tested was compliant with the requirements of Clause 9.3.

Test Engineer(s): Jonathan Chao

Test Date(s): 06/23/11

Discharge Type	Test Voltage ($\pm\text{kV}$)	Results				Anomalies
		Front	Back	Left	Right	
HCP	2	Pass	N/A	N/A	N/A	None
	4	Pass	N/A	N/A	N/A	None
VCP	2	Pass	Pass	Pass	Pass	None
	4	Pass	Pass	Pass	Pass	None
Contact Discharge	2	Pass	N/A	N/A	N/A	None
	4	Pass	N/A	N/A	N/A	None
Air Discharge	2	Pass	Pass	Pass	Pass	None
	4	Pass	Pass	Pass	Pass	None
	6	Pass	Pass	Pass	Pass	None
	8	Pass	Pass	Pass	Pass	Refer to Anomalies list below


Table 15. Electrostatic Discharge, Test Results

Detailed List of Anomalies:


+8kv Air discharge on Ethernet port of the WS5: Hardware error is displayed on the LAN connection (wireless connection shows no anomaly) but is automatically recoverable without manual intervention.

-8kv Air discharge on Ethernet port of the WS5: "Hardware error" or "Request timed out" is displayed on the LAN connection (wireless connection shows no anomaly) but is automatically recoverable without manual intervention.

Electrostatic Discharge




Photograph 9. ESD, Test Points, Back POE



Photograph 10. ESD, Test Points, Front POE

X = Contact Discharge
O = Air Discharge



Photograph 11. ESD, Test Points, Front View



Photograph 12. ESD, Test Points, Left POE

X = Contact Discharge
O = Air Discharge




Photograph 13. ESD, Test Points, Right POE



Photograph 14. ESD, Test Points, Top POE

X = Contact Discharge
O = Air Discharge



Photograph 15. Electrostatic Discharge, Test Setup

Electromagnetic Compatibility Immunity

4.3 Fast Transient, Common Mode

Test Requirement(s): ETSI EN 300 489-1, Clause 9.4:

Per *EN 61000-4-4*, The EUT was tested with the electrical fast transients shown in Figure 3, having an amplitude of ± 1 kV applied to the AC power cables (plug type); ± 0.5 kV applied to the DC power cables; ± 0.5 kV applied to I/O and data lines. Only cables that could potentially exceed 3 m in length in real-world application of the EUT need be tested. Performance criterion B applies for all tests.

Test Procedure:

The EUT was placed on a non-metallic table above a GRP extending at least 1 m beyond all sides of the EUT (See Photograph 16). The Electrical Fast Transient/Burst (EFT/B) generator and the coupling clamp were mounted to the ground plane. For application of the fast transients to the power lines, power was supplied to the EUT through the EFT/B generator. For application of the fast transients to I/O, data and control lines, the cables were individually placed in the coupling clamp, which was also connected to the EFT/B generator.

The EFT/B generator was operated to couple the required transient bursts to each line of the power input in common mode. Transient bursts were applied for a period not less than one minute with both positive transients and negative transients.

The EUT was then powered from an isolated circuit, and selected I/O, data and control cables were placed one at a time in the capacitive coupling clamp. The EFT/B generator was operated to inject the required bursts onto each selected cable via the coupling clamp.

Throughout testing, the EUT was monitored closely for signs of susceptibility.

Electromagnetic Compatibility Immunity

Fast Transient, Common Mode




Figure 3. EN 61000-4-4 Test Waveform

Electromagnetic Compatibility Immunity

Fast Transient, Common Mode

Test Results: The EUT as tested was found compliant with the requirements of Clause 9.4.


Test Engineer(s): Jonathan Chao

Test Date(s): 06/23/11


Port Name	Slot/EUT Side	Test Level	PASS	Anomalies
AC Power				
Phase	POE/ AC Input	± 1 kV	Pass	None
Neutral	POE/ AC Input	± 1 kV	Pass	None
Ground	POE/ AC Input	± 1 kV	Pass	None
Port Name	Slot/EUT Side	Test Level	PASS	Anomalies
I/O Cables & DC Power				
LAN Ethernet Cable	POE/LAN Port	± 0.5 kV	Pass	None

Table 16. Fast Transient, Test Results

Fast Transient, Common Mode



Photograph 16. Fast Transient, Common Mode, Test Setup



Photograph 17. Fast Transient, Common Mode, Telecom Setup

Electromagnetic Compatibility Immunity

4.4 Radio Frequency, Common Mode

Test Requirement(s): ETSI EN 300 489-1, Clause 9.5:

Per *EN 61000-4-6*, all interconnecting cables on the EUT including AC power lines, data and control lines shall be tested for immunity to conducted radio frequencies in the range 0.15 MHz - 80 MHz. Using the bulk current injection method, I/O and data cables must be tested to a level of 3 Vrms. The injection voltage shall be amplitude modulated at 80% by a 1 kHz tone.

Test Procedure:

The EUT was placed on a non-metallic table above a GRP extending at least 1 m beyond all sides of the EUT (See Photograph 18). For power line cables, a Coupling Decoupling Network (CDN) was used. The CDN was initially calibrated in a calibration jig with a 50 Ω RF load and a 100 Ω matching resistor on one side, and a 100 Ω matching resistor and the receiver (spectrum analyzer) on the other. The injection voltage level was adjusted to maintain a monitored voltage of 3 Vrms across the frequency range (0.15 MHz to 80 MHz).

For cables other than the power line in the frequency range 0.15 MHz - 80 MHz, the BCI was initially calibrated in a calibration jig with a 50 Ω RF load and a 100 Ω matching resistor on one side, and a 100 Ω matching resistor and the receiver (spectrum analyzer) on the other. The injection voltage level was adjusted to maintain a monitored voltage of 3 Vrms across the frequency range (0.15 MHz to 80 MHz). The BCI was clamped around the cable under test at a distance of 0.1 to 0.3 m from the EUT.

Electromagnetic Compatibility Immunity

Radio Frequency, Common Mode

Test Results: The EUT as tested was found compliant with the requirements of Clause 9.5.


Test Engineer(s): Jonathan Chao

Test Date(s): 06/22/11


Slot/EUT Side	Port Name	Results / Anomalies
AC Power on back of POE	AC Power Cable	Pass
Ethernet port on front of POE	Ethernet LAN Port	Pass

Table 17. Conducted Immunity, Test Results

Radio Frequency, Common Mode



Photograph 18. Radio Frequency, Common Mode, Test Setup



Photograph 19. Radio Frequency, Common Mode, Telecom Setup

Electromagnetic Compatibility Immunity

4.5 Voltage Dips and Short Interruptions

Test Requirement(s): ETSI EN 300 489-1, Clause 9.7:

Per EN 61000-4-11, the EUT shall be tested for the following voltage dips, interruptions and variations:

5.2.4.4 Voltage Dips and Short Interruptions		
Unit	Test level and Characteristic	Performance Criterion
Voltage reduction %	70% residual voltage for 25 cycles	B
Voltage Interruption	0% residual voltage for 1 cycle	C
Voltage Interruption	0% residual voltage for 1/2 cycle	C
Voltage Interruption	0% residual voltage for 250 cycles	C

Table 18. Voltage Dips and Short Interruptions Limits

Test Procedure: The EUT was placed on a non-metallic table and situated in the center of a GRP. The EUT was provided with AC power via the programmable power supply (See Photograph 20). The power supply was programmed to perform the applicable set of voltage dips, interruptions and variations. Each sequence was repeated three times to verify the results.

Results: The EUT as tested was found compliant with the requirements of Clause 9.7.

Test Engineer: Jonathan Chao


Test Date: 06/23/11

Test Type	Parameters	No of Rep.	Results	Anomalies
Voltage Dips	0% residual voltage for 1/2 cycle	3	Pass	None
Voltage Dips	0% residual voltage for 1 cycle	3	Pass	None
Voltage Dips	70% residual voltage for 25 cycles	3	Pass	None
Voltage Interruption	0% residual voltage for 250 cycles	3	Pass	EUT turns off but recovers without manual intervention and degradation

Table 19. Voltage Dips and Interruptions, Test Results

Electromagnetic Compatibility Immunity

Voltage Dips and Short Interruptions



Photograph 20. Voltage Dips and Interruptions, Test Setup

Electromagnetic Compatibility Immunity

4.6 Surges

Test Requirement(s): ETSI EN 301 489-1, Clause 9.8:

The EUT was tested with the surge waveforms shown on the following page, having an open circuit amplitude of ± 1 kV applied to the I/O interconnection cables. Performance criterion A applies for I/O cables.

The EUT was tested with the surge waveforms shown on the following page, having an open circuit amplitude of ± 1 kV (differential mode), and ± 2 kV (common mode) applied to the AC power cables.

Test Procedure:

The EUT was placed on a non-metallic table above a GRP extending at least 1 m beyond all sides of the EUT (See Photograph 21). For I/O port surges, For application of the fast transients to I/O, data and control lines, the cables were individually placed in the coupling clamp, which was also connected to the EFT/B generator. These three tests were performed with positive surges and negative surges. For other I/O interconnection lines, a coupling de-coupling network [CDN] is required in order to avoid possible adverse effects on equipment not under test and to provide sufficient decoupling impedance to the surge wave so that the specified wave may be developed on the lines under test. The length of the interconnection line between the CDN and the EUT shall be 2 m or shorter.

AC power [where applicable] was supplied to the EUT through the Combination Wave Generator. The combination wave generator was configured to produce the following output:

Open Circuit Voltage:	Front Time = 1.2 μ s Time to Half = 50 μ s
Short Circuit Current:	Front Time = 8 μ s Time to Half = 20 μ s
Telecom wave parameters:	Front Time = 10 μ s Time to Half = 700 μ s

Table 20. Combination Wave Generator Test Parameters for EN 61000-4-5

Electromagnetic Compatibility Immunity

Surges




Figure 4. EN 61000-4-5 Surge Test Waveforms

Electromagnetic Compatibility Immunity

Surges

Test Procedure
(Continued):

For AC power lines, the Combination Wave Generator was operated to couple the required surges between each EUT input power phase and ground, and from line to line. These three tests were performed with positive surges and negative surges, synchronized with the power input phase at 0°, 90°, 180°, and 270°. Throughout testing, the EUT was monitored closely for signs of susceptibility. For I/O port surges, surge waveforms were applied via a CDN, in accordance with *Section 7 of EN 61000-4-5*. The CDN coupled the required surges between each EUT input line and ground, and from line to line. These three tests were performed with positive surges and negative surges.

Test Results: The EUT as tested was found compliant with the requirements of Clause 9.8.

Test Engineer(s): Jonathan Chao


Test Date(s): 06/24/11 – 07/07/11

Port Name	Phase	Test Level	Results	Anomalies
AC, Differential Mode				
Phase to Neutral	0	± 1.0 kV	Pass	None
	90	± 1.0 kV	Pass	None
	180	± 1.0 kV	Pass	None
	270	± 1.0 kV	Pass	None
AC, Common Mode				
Phase to Ground	0	± 2.0 kV	Pass	See Anomalies List
	90	± 2.0 kV	Pass	See Anomalies List
	180	± 2.0 kV	Pass	See Anomalies List
	270	± 2.0 kV	Pass	See Anomalies List
Neutral to Ground	0	± 2.0 kV	Pass	See Anomalies List
	90	± 2.0 kV	Pass	See Anomalies List
	180	± 2.0 kV	Pass	See Anomalies List
	270	± 2.0 kV	Pass	See Anomalies List
Port Name / Coupling	Phase	Test Level	Results	Anomalies
IO, Differential Mode				
Phase to Neutral POE Port	N/A	± 1.0 kV	Pass	None
Phase to Neutral LAN Port	N/A	± 1.0 kV	Pass	None

Table 21. Surges, Test Results

Detailed List of Anomalies:
Phase to Ground at +1kV at 0, 90, 180, 270 degree: “Hardware error” and “Request time out” are displayed on the LAN connection (no errors on wireless connection). Unit recovers normal functions without manual intervention.
Phase to Ground at -1kV at 0, 90, 270 degree: “Hardware error” and “Request time out” are displayed on the LAN connection (no errors on wireless connection). Unit recovers normal functions without manual intervention.
Phase to Ground at +2kV at 0, 90, 180, 270 degree: “Hardware error” and “Request time out” are displayed on the LAN connection (no errors on wireless connection). Unit recovers normal functions without manual intervention.
Phase to Ground at -2kV at 0, 90, 180, 270 degree: “Hardware error” and “Request time out” are displayed on the LAN connection (no errors on wireless connection). Unit recovers normal functions without manual intervention.
Neutral to Ground at +1kV at 0, 90, 180, 270 degree: “Hardware error” and “Request time out” are displayed on the LAN connection (no errors on wireless connection). Unit recovers normal functions without manual intervention.
Neutral to Ground at -1kV at 0, 90, 180, 270 degree: “Hardware error” and “Request time out” are displayed on the LAN connection (no errors on wireless connection). Unit recovers normal functions without manual intervention.
Neutral to Ground at +2kV at 0, 90, 180, 270 degree: “Hardware error” and “Request time out” are displayed on the LAN connection (no errors on wireless connection). Unit recovers normal functions without manual intervention.
Neutral to Ground at -2kV at 0, 90, 180, 270 degree: “Hardware error” and “Request time out” are displayed on the LAN connection (no errors on wireless connection). Unit recovers normal functions without manual intervention.

Surges



Photograph 21. Surges, Test Setup



Photograph 22. Surges, I/O Test Setup

5.0 Test Equipment

Calibrated test equipment utilized during testing was maintained in a current state of calibration per the requirements of ANSI/NCSL Z540-1-1994 and ANSI/ISO/IEC 17025:2000.

Test Name: AC Conducted Emissions Voltage Clause 8.4			Test Date(s): 06/21/11		
MET Asset #	Nomenclature	Manufacturer	Model	Last Cal Date	Cal Due Date
1S2607	SPECTRUM ANALYZER	AGILENT	E4407B	7/30/2010	7/30/2011
1S2678	LISN DUAL LINE V-NETWORK	TESEQ	NNB 51	12/1/2010	12/1/2011
Test Name: Harmonic Current Emissions Clause 8.5			Test Date(s): 06/22/11		
MET Asset #	Nomenclature	Manufacturer	Model	Last Cal Date	Cal Due Date
1S2398	POWER MEASUREMENT SYSTEMS	COMBINOVA	ANALYZER 300	04/19/2011	04/19/2012
Test Name: Voltage Fluctuations (Flicker) Clause 8.6			Test Date(s): 06/22/11		
MET Asset #	Nomenclature	Manufacturer	Model	Last Cal Date	Cal Due Date
1S2398	POWER MEASUREMENT SYSTEMS	COMBINOVA	ANALYZER 300	04/19/2011	04/19/2012
Test Name: Telecom Line Conducted Emissions Clause 8.7			Test Date(s): 06/21/11		
MET Asset #	Nomenclature	Manufacturer	Model	Last Cal Date	Cal Due Date
1S2607	SPECTRUM ANALYZER	AGILENT	E4407B	7/30/2010	7/30/2011
1S2678	LISN DUAL LINE V-NETWORK	TESEQ	NNB 51	12/1/2010	12/1/2011
1S2653	AMPLIFIER	SONOMA INSTRUMENT	310 N	SEE NOTE	
Test Name: Radiated Electromagnetic Field Clause 9.2			Test Date(s): 06/21/11		
MET Asset #	Equipment	Manufacturer	Model	Last Cal Date	Cal Due Date
1S2576	AMPLIFIER 80-1000MHZ	AMPLIFIER RESEARCH	500W1000A	SEE NOTE	
1S2478	TWT AMPLIFIER 1-2500MHZ	COMMUNICATIONS & POWER INDUSTRIES	VZL6943J2	SEE NOTE	
1S2473	AMPLIFIER 2500MHZ-4000GHZ	HUGHES	1277H01F000	SEE NOTE	
1S2401	BILOG ANTENNA	SCHAFFNER	CBL6140A	SEE NOTE	
1S2208	HORN ANTENNA	EMCO	3115	07/29/2010	07/29/2011
1S2579	ISOTROPIC ELECTRIC FIELD PROBE	ETS-LINDGREN	HI-6053	11/10/2010	11/10/2011
1S2264	CHAMBER 3	LINDGREN RF ENCLOSURES	IMMUNITY CHAMBER	7/29/2010	7/29/2011
1S2409	SIGNAL GENERATOR	GIGATRONICS	6062A	11/30/2010	11/30/2011
Test Name: Electrostatic Discharge Immunity Clause 9.3			Test Date(s): 05/06/11		
MET Asset #	Equipment	Manufacturer	Model	Last Cal Date	Cal Due Date
1S2470	ELECTROSTATIC DISCHARGE GUN & SIMULATOR	NOISE LABORATORY	TC-815R & ESS-2000	5/19/2011	5/19/2012

Test Name: Fast Transients Clause 9.4			Test Date(s): 06/23/11		
MET Asset #	Equipment	Manufacturer	Model	Last Cal Date	Cal Due Date
1S2656	TRANSIENT 2000	EMC PARNTER	TR2000:2000; CDN:2000A-06-63; CN: EFT 1000	SEE NOTE	
Test Name: Radio Frequency, Conducted Continuous Clause 9.5			Test Date(s): 06/22/11		
MET Asset #	Equipment	Manufacturer	Model	Last Cal Date	Cal Due Date
1S2514	ATTENUATOR	JFW	50FH-003-300	SEE NOTE	
1S2578	AMPLIFIER	AMPLIFIER RESEARCH	75A250A	SEE NOTE	
1S2390	SIGNAL GENERATOR	GIGATRONICS	6061A	6/24/2010	6/24/2011
1S2649	SPECTRUM ANALYZER	AGILENT	E4401B	SEE NOTE	
1S2487	RF CURRENT PROBE	SOLAR ELECTRONICS	6741-1	2/21/2011	2/21/2012
1S2586	CDN	COM-POWER	CDN-M325	SEE NOTE	
Test Name: Voltage Dips and Short Interruptions Clause 9.7			Test Date(s): 06/23/11		
MET Asset #	Equipment	Manufacturer	Model	Last Cal Date	Cal Due Date
1S2656	TRANSIENT 2000	EMC PARNTER	TR2000:2000; CDN:2000A-06-63; CN: EFT 1000	SEE NOTE	
Test Name: Surges Clause 9.8			Test Date(s): 06/24/11 – 07/07/11		
MET Asset #	Equipment	Manufacturer	Model	Last Cal Date	Cal Due Date
1S2656	TRANSIENT 2000	EMC PARNTER	TR2000:2000; CDN:2000A-06-63; CN: EFT 1000	SEE NOTE	

Note: Functionally verified test equipment is verified using calibrated instrumentation at the time of testing.